







工事件名	国宝金峯山寺二王門素屋根建設工事						集計表	1 / 1											
工事科目	電灯分岐								新設										
図番:																			
縮尺:							計上	NO.	1/1	2/2									
名称	摘要		区分	単位	合計														
照明器具	A431			台	90.0	90.0	90.0												
照明器具	B3200			台	10.0	10.0	10.0												
照明器具	C370			台	5.0	5.0	5.0												
ブルボックス	B	400*400*400 SUS WP		個	5.0	5.0	5.0												
ブルボックス	C	300*300*300 SUS WP		個	6.0	6.0	6.0												
ブルボックス	D	250*250*200 SUS WP		個	31.0	31.0	31.0												
ブルボックス	E	200*200*200 SUS WP		個	16.0	16.0	16.0												
露出ボックス		1~4方出		個	81.0	81.0	81.0												
露出スイッチボックス		1個用		個	1.0	1.0	1.0												
露出スイッチボックス		2個用		個	4.0	4.0	4.0												
自動点滅器				個	1.0	1.0	1.0												
埋込スイッチ		1P15A*3		個	1.0	1.0	1.0												
埋込スイッチ		1P15A*4		個	1.0	1.0	1.0												
埋込スイッチ		1P15A*6		個	2.0	2.0	2.0												
ケーブル		EM-EEF2.0-2C	管内	m	67.0	67.2	67.2												
ケーブル		EM-EEF2.0-3C	管内	m	1,070.0	1,069.7	1,069.7												
電線管		CP25	露出	m	494.0	493.8	493.8												
電線管		CP31	露出	m	223.0	222.5	222.5												
電線管		CP51	露出	m	151.0	150.5	150.5												
電線管		CP63	露出	m	14.0	13.7	13.7												
誘導標識				枚	24.0	24.0	24.0												











工事件名	国宝金峯山寺二王門素屋根建設工事														拾出	1 / 2												
工事科目	コンセント分岐														新設			立上・立下										
図番:	階高																											
縮尺:	天井高																											
名称	摘要		区分	単位	計																							
ケーブル	EM-EEF2.0-3C	(CP25)	管内	m	268.7	3.7	2.4	1.0	3.7	1.0	3.7	3.7	3.7	3.7	3.7	0.8	1.8	1.0	7.8	1.0	3.7	3.7	2.3	3.7	3.7	3.7	1.0	
						3.7	1.0	2.8	3.7	1.0	3.7	2.8	1.2	2.3	2.8	2.4	1.0	1.0	2.8	2.8	2.8	2.8	2.8	2.8	2.8	1.0	1.0	2.8
						2.8	2.8	2.8	2.8	5.0	2.8	2.3	2.8	2.8	5.7	2.8	2.8	2.8	1.0	2.8	1.0	2.8	1.0	0.5	1.0	3.6	3.6	
						3.6	3.6	3.6	3.6	0.5	0.5	3.6	3.6	3.6	3.6	3.6	2.4	3.6	0.5	0.5	0.5							
						6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0	6.0														
ケーブル	EM-EEF2.0-3C *2	(CP31)	管内	m	16.0	7.0	2.9	2.9	3.2																			
ケーブル	EM-CE5.5-3C	(CP31)	管内	m	32.0	4.6	5.1	2.8	4.6	5.1	2.7	2.7	2.2	2.2														
ケーブル	EM-CE5.5-3C *2	(CP51)	管内	m	73.6	2.3	5.0	6.6	2.3	2.8	2.5	2.6	9.3	2.4	3.2	1.2	4.6	4.4	2.5	2.6	2.9	7.4	7.8	1.2				
ケーブル (A)	EM-CE5.5-3C *2	(CP51)	管内	m	41.5	7.1	7.4	7.8	4.9	2.3	3.0	9.0																
ケーブル (B)	EM-CE5.5-3C *2	(CP51)	管内	m	48.2	0.8	10.8	2.3	3.0	3.9	2.8	3.4	3.1	4.1	5.0	9.0												
ケーブル (C)	EM-CE5.5-3C *2	(CP51)	管内	m	39.3	9.0	7.8	7.4	7.8	1.5	3.2	2.6																
ケーブル (D)	EM-CE5.5-3C *3	(CP51)	管内	m	33.0	1.3	7.8	2.4	2.3	1.5	7.8	7.4	2.5															
ケーブル (E)	EM-CE5.5-3C *3	(CP51)	管内	m	43.4	4.0	4.7	3.2	1.2	7.8	7.4	7.8	1.5	3.2	2.6													
ケーブル (F)	EM-CE5.5-3C *2	(CP51)	管内	m	28.7	4.7	1.3	7.8	2.4	3.2	1.5	7.8																
ケーブル (G)	EM-CE5.5-3C	(CP31)	管内	m	174.7	7.1	7.4	7.8	4.9	0.8	10.8	2.3	3.0	3.9	2.8	3.4	3.1	4.1	5.0	9.0	7.8	7.4	7.8	1.5	3.2	2.6	1.3	
						7.8	2.4	2.3	1.5	7.8	7.4	2.5	4.7	1.5	3.2	2.6	1.3	7.8	2.4	3.2	1.5	7.8						















工事件名	国宝金峯山寺二王門素屋根建設工事					集計表	1 / 1							
工事科目	雷保護設備							新設						
図番:														
縮尺:						計上	NO.	2/2						
名称	摘要	区分	単位	合計										
受電導体 アルミ線 (鬼燃線) 20/2.5			m	190.0	189.6	189.6								
アルミ線取付金物 屋根用			個	220.0	220.0	220.0								
T型・十字型接続金物			組	21.0	21.0	21.0								
引下導線 アルミ線 (鬼燃線) 20/2.5			m	180.0	180.0	180.0								
アルミ線取付金物 鉄骨用			個	156.0	156.0	156.0								
ビニール管VE(28)			m	24.0	24.0	24.0								
ビニール管取付金物 鉄骨用			個	24.0	24.0	24.0								
接地用端子箱 露出用 SUS製			面	6.0	6.0	6.0								
A型接地極			個所	12.0	12.0	12.0								
接地線 銅線 (鬼燃線) 2.0/19			m	60.0	60.0	60.0								
C型コネクタ			個	12.0	12.0	12.0								
手摺用接続金物			組	4.0	4.0	4.0								
水平環状導体 アルミ線 (鬼燃線) 20/2.5			m	120.0	120.0	120.0								
アルミ線取付金物 鉄骨用			個	140.0	140.0	140.0								



















